



| | |
|------------|---------------|
| REV | 01 |
| Data | February 2022 |
| Supersedes | N/A |

Service Manual

Startup Guide – EWAD-TZB, EWAH-TZB, EWAD-TZC, EWAH-TZC, EWAD-MZB, EWAD-MZC



Contents

| | |
|--|-----------|
| 1 Technician Qualifications | 3 |
| 2 Required Tools and Supplies..... | 3 |
| 3 Collaboration and Responsibilities | 4 |
| 4 Before Arriving at Jobsite | 4 |
| 5 Upon Arrival at Jobsite..... | 4 |
| 6 Pre-Power on Checks | 5 |
| 6.1 Visual Inspection..... | 5 |
| 6.2 Leak Test | 5 |
| 6.3 Water Piping System Check | 5 |
| 6.4 Water Flow..... | 5 |
| 6.5 Electric Connections Check | 6 |
| 7 Pre-Startup Checks..... | 7 |
| 7.1 Voltage Check..... | 7 |
| 7.2 Flow Switches | 7 |
| 7.3 Control Settings | 7 |
| 7.3.1 Unit Configuration | 7 |
| 7.3.2 Circuit configuration | 8 |
| 7.3.3 Software Options | 9 |
| 7.4 Fan layout | 11 |
| 7.5 Twin evaporator pump setting..... | 11 |
| 7.6 Alarm Limits | 11 |
| 7.7 Energy Meter | 11 |
| 7.8 Pre-Running Adjustments | 14 |
| 7.8.1 Check and calibration of unit temperature sensors | 14 |
| 7.8.2 Check and calibration of circuit temperature sensors | 14 |
| 7.9 Dry Tests | 15 |
| 7.9.1 Unit Alarm | 16 |
| 7.9.2 7.9.2 Pump #1/#2..... | 16 |
| 7.9.3 Circuit Alarm | 16 |
| 7.9.4 Fan..... | 16 |
| 7.9.5 Oil/VFD Heaters..... | 16 |
| 7.9.6 7.9.6 VR Slides | 16 |
| 7.9.7 Expansion Valve | 16 |
| 7.9.8 Eco Expansion Valve | 16 |
| 7.9.9 High Pressure Switches Test..... | 16 |
| 7.9.10 Compressor addressing..... | 16 |
| 8 Start-Up..... | 17 |
| 8.1 Running Adjustments..... | 17 |
| 8.1.1 Check and calibration of pressure transducers | 17 |
| 8.1.2 Subcooling measurement point | 18 |
| 8.2 Running Safeties Test..... | 19 |
| 8.2.1 Flow Switches | 19 |
| 8.3 Data acquisition | 19 |
| 9 TABLES | 19 |
| 9.1 Unit Layout (Table A) | 19 |
| 9.1.1 EWAD/H TZ-B and EWAD-MZB layout..... | 19 |
| 9.1.2 EWAD TZ-C, EWAH TZ-C, EWAD-MZ-C layout..... | 22 |
| 9.2 Unit configuration (Table B) | 25 |
| 9.2.1 EWAD TZ-C, EWAH TZ-C | 25 |
| 9.2.2 EWAD MZ-C | 26 |
| 9.2.3 EWAD TZ-B and EWAH TZ-B | 26 |
| 9.2.4 EWAD MZ-B | 29 |
| 9.3 Pump Inverter Settings (Table C)..... | 30 |
| 9.4 Pre-Commissioning Sheet (Table D) | 31 |
| 9.5 Commissioning Sheet (Table E) | 32 |

1 Technician Qualifications

Initial startup on Daikin chillers must be performed only by Daikin Service Technicians or Authorized Service Providers. The contents of this manual are not intended as a substitute for professional skills training, or knowledge and practice of industry standards. Additional literature will be required that is product and component specific, including: product Installation Manuals, Service Bulletins, selection data, system control and piping specifications, etc. (see List of References on *Paragraph 2* for a list of some supplemental items).



The following information is intended only as a guide for authorized personnel with a sound basic knowledge of HVAC equipment, mechanical systems, electrical wiring, controls, & microprocessors. Attempts by untrained or unauthorized persons to start, operate and service this equipment can result in equipment failure, personal injury, or death, as well as invalidation of product warranty. It is the responsibility of the technician to ensure that proper safety equipment safe practices are used.

Be sure that before beginning any work, the Startup Service Technician has reviewed and is thoroughly familiar with all Daikin Factory Service Safety Policies and Procedures and has reviewed any Service Bulletins or Rapid News regarding this product.

2 Required Tools and Supplies

In addition to standard tools needed on most service jobs, be sure to bring the following items to the jobsite for Startup:

- ☒ Personal Protective Equipment (Safety)
- ☒ Commissioning Sheet
- ☒ Chiller Technical Data, Selection Sheet, and Certified Submittal Drawings
- ☒ Manuals:
 - Note: Be sure that all manuals are the current revision appropriate for this unit.*
 - This Manual: Startup Guide – EWAD-TZB, EWAH-TZB, EWAD-TZC, EWAH-TZC, EWAD-MZB, EWAD-MZC
 - Installation, Operation and Maintenance Manual Air cooled chiller with inverter driven screw compressor (D-EIMAC01603-18_03EN)
 - Control Manual: Air cooled chiller with inverter driven screw compressor (D-EOMZC00309-19_02EN)
 - EWAD_TZ P&ID (last revision) – check in IOM Manual
 - Wiring Diagram
- ☒ Other technical reference material as necessary
- ☒ Current operating software version downloaded and ready to install if needed:
 - Last ATLAS version available on official repository
- ☒ Miscellaneous gauges and hand tools, including:
 - Electronic Leak Detector
 - Differential Pressure Gauge (*adequate for system pressures*)
 - Phase Rotation Meter
 - Refrigeration Gauge Manifold (*Range: 50bar, Accuracy: ±0.5% of Final Value, Resolution: 0.01bar/0.1psi/1kPa*)
 - Digital thermometer (*Range: -50°C/+150°C, Accuracy: ±0.1°C, Resolution: 0.1°C*)
 - Amp probe
 - Voltmeters
 - Recover refrigerant cylinder (*for eventual charge adjustments*)
 - Full refrigerant cylinder (*for eventual charge adjustments*)
 - Recovery pump (*for eventual charge adjustments*)

3 Collaboration and Responsibilities

Throughout the installation and startup process, members of the Daikin Service Department (Supervisor / Coordinator / Technician) must establish contact and meet regularly with the following persons and/or their designated representatives:

- Mechanical, Electrical, and Controls Contractors
- Installing Contractor
- Daikin Sales Department
- Customer/Owner
- Personnel to be trained in unit operation

It is the responsibility of the Daikin Service Representative to ensure that all items on the *Pre-Power On Checklist* are complete and the system is ready for start-up. Upon arrival at the jobsite, the DAIKIN Service technician will verify that all items on the *Pre-Power On Checklist* are complete.

The Chiller Start-up Technician must confirm that the unit installation conforms to Daikin specifications and requirements. This includes mounting and support, piping, electrical and control installations related to the unit. These items must, as a minimum, meet acceptable industry standards and Daikin published requirements. All factory supplied controls and valves must be set and, where required, calibrated. Electrical power and control wiring must be selected and sized as specified by Daikin and the applicable electrical code.

The various contractors associated with the installation have the responsibility to provide the following items (as noted on the Pre-Start Checklist), in accordance with the product IOM, applicable codes and acceptable practices for the trade involved. Note any discrepancies on Commissioning Sheet and notify Supervisor as appropriate. Ensure that access to appropriate systems is available for startup operations.

4 Before Arriving at Jobsite

- Review and Verify Pre-Commissioning Sheet received from the Installer/Customer (*Table D*) Company/Contractor.
- Review Required Materials List on (refer to paragraph 2) and gather necessary items.
- Review Unit Design Specifications.
- Review Unit Selection Sheet.
- Review Startup Guide and Commissioning Form.
- Review IOM.
- Review Control Manual.
- Establish estimated timeline and milestones for Startup.

5 Upon Arrival at Jobsite

Meet with Mechanical, Electrical, and Control Contractors to discuss Startup Process and identify any potential issues that may interfere with a successful startup.

Be sure to meet with the Controls Contractor to discuss and clarify the chiller control sequence and settings for the chiller, towers, pumps, BAS integration, etc...

6 Pre-Power on Checks

Initial Chiller Inspection has to be performed according to the **Pre-Power On Checklist** of the Commissioning Sheet by following the instruction below shown.



Verify that all the items are correct. If the system is not ready and/or items on the Pre-Power On Checklist are incomplete, the technician should immediately notify his supervisor and request direction on how to proceed. A separate work order authorization may be required.

6.1 Visual Inspection

- Inspect the chiller for shipping/installation damage including fans and internal parts of condenser.
- Verify that chiller is adequately located, and level mounted as per the IOM (**Paragraph 4.4**) according to the minimum space requirements (**Paragraph 4.5**)
- Verify that appropriate anti-vibration pads are installed.
- Visually inspect for oil and refrigerant leaks.
- Record component model and serial numbers as appropriate on Commissioning Form.
- Clean the chiller from any foreign debris and surrounding area.

Note any issues in the Commissioning Form (**Pre-Startup Comments**)

6.2 Leak Test

Before to start with Leak Test, verify that during stock period (from Delivery Date), leak tests have been performed periodically as per local FGas Regulation. Collect all leak test reports for recording purpose.

Connect service gauges. Confirm pressure in the condenser and evaporator, to verify that charge was not leaked during storage/shipping. Using Electronic Leak Detector, leak check entire unit. Be sure to note any leaks found and repairs performed on the Commissioning Sheet. Follow all applicable industry and regulatory authority standards. If refrigerant loss is catastrophic, startup may need to be postponed until appropriate warranty leak repairs are completed.

Note any issues in the Commissioning Form (**Pre-Startup Comments**)

6.3 Water Piping System Check

- Verify water piping as per IOM (**Paragraph 4.7**). The water filter must be installed as close as possible to the chiller, as in Figs. 8 and 9. If the water filter is installed in another part of the water system, the Installer has to guarantee the cleaning of the water pipes between the water filter and the evaporator. Missing filter results withdraw of heat-exchangers warranty.
- Verify if proper glycol percentage for the application in accordance with Daikin specifications is present as per IOM (Paragraph 2.12)
- Walk length of piping system (in equipment area). Ensure that connections are correctly installed, and piping is properly supported (i.e., not supported by the chiller). Flanges must not be stressed.
- Check evaporator piping for proper flow direction through vessels by consulting Dimensional Drawing. If flow is incorrect, notify Mechanical Contractor, Service Supervisor, and Sales Rep.
- Verify that water pressure gauges are installed at proper locations
- Confirm that all piping specialties (expansion tank, make-up, relief, vents, etc), water pumps are properly installed.

Note any issues in the Commissioning Form (**Pre-Startup Comments**)

6.4 Water Flow

Use Differential Pressure Gauge at the inlet/outlet nozzles of the unit connections to measure the pressure drop across the exchanger/exchangers.

Compare actual flow with Pressure Drop specified on the Unit Selection Sheet. Verify that actual flow is in line with the selection data.




If the measured flow isn't in line with the selection data, then refer to the CSS (Chiller Selection Software) for the verification of allowability of the measured water flow.

If flow is outside of acceptable margins, corrective action is required. If flow is too high, valves may be adjusted to trim flow. If flow is too low, notify Installing Contractor, and note on the Commissioning Form. If flow is different from the selection data, notify Service Supervisor and Sales Rep. Correction may be required prior to startup.

Note any issues in the Commissioning Form (**Pre-Startup Comments**)

6.5 Electric Connections Check

- Verify the Electric connections, Cable requirements, Interconnection cables and Phase unbalance as per IOM.
- Verify the proper electrical phasing U-V-W of the loads (fans, compressors, and pumps) for L1, L2 and L3 respectively.
- Verify Field wiring correctness according to the unit wiring diagram



External power supply needed for Digital output terminals
Analog Inputs must be generated through external auxiliary voltage

Note any issues in the Commissioning Form (**Pre-Startup Comments**)

7 Pre-Startup Checks

Once the “*Pre-Power On Checks*” are completed, the technician can proceed with the Pre-Startup Checks by turning on the unit main switch.

Pre-Startup checks must be performed according to the **Pre-Startup Checklist** of the Commissioning Sheet by following the instruction below shown.



Make sure that unit switch (Q0) is set in OFF state before turning on the unit main switch



Verify that all the items are correct. If the system is not ready and/or items on the Pre-Startup Checklist are incomplete, the technician should immediately notify his supervisor and request direction on how to proceed. A separate work order authorization may be required.

7.1 Voltage Check

- Verify the electric Main voltage and frequency
- Verify all on-board auxiliary transformer voltages
- Check the Compressor Heater current

Note any issues in the Commissioning Form (**Pre-Startup Comments**)

7.2 Flow Switches

- Check the water flow safety switches: verify that field-installed flow switches are installed as per the manufacturer's instructions and IOM.
- Any differential pressure switch connections must be made across the vessel they protect.
- Field-installed Flow switches should not be located close to any source of turbulence and should be located in inlet or outlet piping of the vessel away from any shutoff valves or isolation devices.
- Verify flow switches operation, by throttling the flow and verify that switch opens when flow rate falls below 50% of nominal operating flow rate.

Note any issues in the Commissioning Form (**Pre-Startup Comments**)

7.3 Control Settings

- Check all MicroTech IV controller settings to verify they are optimized for application conditions.
- Download and/or install updated software as needed.
- Verify settings of all safety and operating controls.

7.3.1 Unit Configuration

On the unit controller, enter the “Technician Password” and go into Main Menu → Commission Unit → Configuration → Unit

| Setpoint | Default | Range | Description |
|----------------|-----------|----------------------------|--|
| Apply Changes= | No | No Yes | Use this command to reset the controller in order to confirm the configuration made |
| Unit Type | EWAD TZ B | TZ TZ B TZ C MZ B | Select the type of chiller. EWADxxxTZxx → EWAD TZ EWADxxxTZxxB → EWAD TZ B EWADxxxTZxxC → EWAD TZ C EWAHxxxTZxxB → EWAH TZ B EWAHxxxTZxxC → EWAH TZ C EWADxxxMZxxB → EWAD MZ B EWADxxxMZxxC → EWAD TZ C Note: the model EWAH must be selected as TZ C & EWAD MZ C must be selected as TZ C. |

| | | | |
|-----------------|---------|--|---|
| Refrigerant | R134A | R134A R1234ZE R513A | Select the type of refrigerant |
| Number of Ckts= | 2 | 1 2 | Define the number of circuits |
| Comp Type= | None | Not Set 310240 S 310240 L F4AL VVR 3120 3122 F3AL F3AS F3BL | Select the compressor model according to the machine model, referring to the unit configuration tables (Table B) / compressor nameplates |
| Motor | AC | AC DC | Define the type of compressor motor by referring to the configuration Table B. All EWAD/H TZ C have AC motor compressor |
| Inverter Type | DAE | DAE | All production units are equipped with DAE Inverter |
| Inverter Size | 200kW | 90kW 120kW 200kW 330kW 400kW | Select the type of inverter installed on the compressor. Refer to Table B. |
| Fans Control | Step | Step Vfd SpdTrl | Select whether the fans are Direct-start (On Off) or if they are controlled by inverter by referring to the electrical wiring of the unit. Step = All fans are with direct start (On Off) vfd = All fans are controlled by Vfd Spdtrl = Only one fan is controlled by Vfd and all others are direct starting (On Off) |
| Fan Type= | AC700 | AC700 EC900 AC900 EC900-700 EC700 EC700-600 DC1000-900 EC1400 DC1000 DC1000-700 AC900 AC900-700 | Select the fan type according to the machine model by reference to the unit configuration table (Table B). In case of Kemao fans select AC900 |
| Eco EXV Type= | Sporlan | Sporlan Danfoss Colibri | Select the electronic valve model of the Economizer. The model can be read directly on the engine body of the valve itself |



After termination of the Unit configuration it's necessary to restart the controller to activate the settings made through the "Apply changes" command.

The control part of Micro-channel EWAD/H TZ C, EWAD/H TZ B and EWAD-MZ B/C machines is composed of the controller POL688 + 1 or 2 modules POL98U (depending on whether the machine is Mono or Dual). Once the **unit** has been **configured**, after the controller has been restarted, a part of the program will be automatically be transferred on the POL98U modules. Be careful not to remove the power supply if the BSP and BUS LEDs of both POL98U modules have become green.

7.3.2 Circuit configuration

Technician Password -> Commission Unit -> Configuration -> circuit #1/circuit #2

| Setpoint | Default | Range | Description |
|----------------|---------|-------|-------------|
| Apply Changes= | No | | No, Yes |

| | | | |
|-----------------|---------|---|--|
| Comp Freq | - | Compressor 310240 S: 60 Hz; 65 Hz; 70 Hz; 75 Hz; 80 Hz; 85 Hz; 90Hz; 95 Hz; 100 Hz; 105 Hz; 110 Hz; Compressor 310240 L: 60 Hz; 65 Hz; 70 Hz; 75 Hz; 80 Hz; 85 Hz; 90 Hz; 95 Hz; 100 Hz; 105 Hz; 110 Hz; Compressor F4AL VVR: 50 Hz; 55 Hz; 60 Hz; 65 Hz; 70 Hz; 75 Hz; 80 Hz; | Select the maximum compressor frequency according to the machine model by referring to the configuration tables. (Table B) |
| C1/2 # Of Fans= | 6 | | Enter the number of fans present on the machine. When the fans are all vfd controlled, this parameter can be changed between 1 and 2. <u>Always leave the setting to 2.</u> When configuring the number of fans in EWAD TZ C unit, <u>be careful never to set an odd number of fans!</u> |
| Heat Recovery= | Disable | Disable, Enable | Select whether the <u>total heat</u> recovery option, is present. |



After termination of the circuit(s) configuration it's necessary to restart the controller to activate the settings made through the "Apply changes" command.

7.3.3 Software Options

Software Options (Only for Microtech 4)



The possibility to employ a set of software options has been added to the functionality of the chiller, in according with the new Microtech 4 installed on the Unit. The Software Options do not require any additional hardware and regard communication channels and the new energy functionalities.

During the commissioning the machine is delivered with the Option Set chosen by the customer; the Password inserted is permanent and depends on the Serial Machine Number and the Option Set selected.

The available options are:

1. Modbus Slave MSTP for settings refer to BAS integration guide Doc. Name: D-EIGOC00203-21EN_TZ
2. BACNet MSTP for settings refer to BAS integration guide Doc. Name: D-EIGOC00103-21EN-TZ
3. BACNet IP for settings refer to BAS integration guide Doc. Name: D-EIGOC00103-21EN-TZ
4. Performance Monitoring. The Energy Monitoring is a software option not requiring any additional hardware. It can be activated to achieve an estimation (5% accuracy) of the instantaneous performances of the chiller in terms of:
 - Cooling Capacity
 - Power Input
 - Efficiency-COP
 An integrated estimation of these quantities is provided
5. iCM Standard for settings and configuration contact servicesupport@daikinapplied.eu
6. iCM Advanced for settings and configuration contact servicesupport@daikinapplied.eu

| Apply Changes= | No | | No, Yes |
|----------------|--------|------------------------------------|--|
| Pump Type | On-Off | On-Off Fixed Speed VPF DT | Select whether the evaporator pump (s) are direct-start or if they are controlled by an inverter. ON OFF → Direct Start. Fixed Speed → Allows an automatic pump speed variation, between three different speed settings. VPF → Pump speed is controlled in order to maintain a minimum pressure drop in a remote location of the plant DT → The chiller will modulate the water flow rate based on the chiller delta |

| | | | |
|----------------------|--------------|---|--|
| Load PD Sns | None | None 0-10V 4-20mA BMS | Type of pressure differential sensor used in the VPF system |
| Power Supply | 400V/50-60Hz | 400V/50-60Hz 415V/50Hz 440V/60Hz 460V/60Hz 380V/50-60Hz | Define the voltage grid system: this will determine the undervoltage/overvoltage supervision managed by the compressor inverter |
| Energy Mtr | None | None Nemo D4-L Nemo D4-Le | Select the type of energy meter device in case present  Nemo D4-L  Nemo D4-Le |
| Leak Detector | None | None Digital Analog | Select the type of leak detector device in case present. |
| Communication 1 | None | None Modbus IP MSTP | Select whether a connected communication module is present on the left side of the controller. Modbus -> POL902 BACNet IP -> POL908 BACNet MSTP -> POL904 |
| Communication 2 | None | None Modbus IP MSTP | Select whether a connected communication module is present on the left side of the controller. Modbus -> POL902 BACNet IP -> POL908 BACNet MST -> POL904 |
| Communication 3 | None | None Modbus IP MSTP | Select whether a connected communication module is present on the left side of the controller. Modbus -> POL902 BACNet IP -> POL908 BACNet MST -> POL904 |
| Demand Limit | Disable | Disable Enable | Set according to the client request |
| Flex Current Limit | Disable | Disable Enable | Set according to the client request |
| Setpoint Reset | None | None 4-20mA Return OAT | In case of setpoint reset request, select on the basis of which sensor the reset will be carried out 4-20 mA -> External sensor Return -> EEWT temp sensor OAT -> Unit outside air temp sensor |
| Fan Alarm | No | No Yes | Select this option if the KQ1 and KQ2 relays are present in the electrical panel |
| Switch Box Temp | No | No Yes | Select if the switch box temperature probe is present. (HA units) |
| Rapid Restart | Off | Off On | Enabling the Rapid Restart Function. Check if the option is available on the unit |
| Ext Alarm | Event | Event Rapid Stop | Set according to the client request |
| Loc Net Switch | No | No Yes | Set according to the client request |
| M/S Address | None | None Master Slave 1 Slave 2 Slave 3 | Defines if the unit is master or slave |
| M/S Num Of Units | 2 | 2 3 4 | Set according to the number of units in the system |
| M/S Sns Type | NTC10K | None NTC10K PT1000 | Select the type of sensor for the common water temperature sensor? |
| Display Units | Metric | Metric English | Set according to the client request |
| Language | English | - | Set according to the client request |
| Liquid Sensor Enable | Off | Off On | For Unit Type= TZ-TZB-MZ Select On if the temperature probe and / or pressure transducer are present on the liquid line. If option 186 is present (Performance Monitoring), select On. |

| | | | |
|----------------|----------|------------------|---|
| | | | For Unit Type= TZC For EWAD TZC and EWAHA TZC always select On. |
| Liquid Sensors | Standard | Standard Full | Select Standard if on the liquid line is present the temperature sensor Select Full if on the liquid line is present the temperature sensor and pressure transducer sensor |
| Solenoid valve | Off | Off On | Select always On*. See the Caution after the table |
| Apply Changes | No | No Yes | Use this setting to save and confirm all the settings |



CAUTION

**Solenoid valve setting: This parameter is used to configure the anti-chattering system in the software*

After the apply changes function, verify the activation of the Solenoid Valve in the following menus

*View/Set Circuit > Circuit ½ > Economizer > Sol Valve > **With***

The parameter must be set "With". In case the parameter is "Without", change to "With"



After termination of the Software Options configuration it's necessary to restart the controller to activate the settings made through the "Apply changes" command.

7.4 Fan layout

The image below shows the activation layout of the unit's fans. The number inside the single square indicates the fan activation digital output.

| | | | | | | | | | | | | | | | | |
|------------------|---|---|---|---|---|---|---|---|------------|---|---|---|---|---|---|---|
| Quadro Elettrico | 1 | 4 | 3 | 6 | 5 | 6 | 5 | 6 | 1 | 4 | 3 | 6 | 5 | 6 | 5 | 6 |
| | 4 | 2 | 4 | 5 | 6 | 5 | 6 | 6 | 4 | 2 | 4 | 5 | 6 | 5 | 6 | 6 |
| Circuito 2 | | | | | | | | | Circuito 1 | | | | | | | |

7.5 Twin evaporator pump setting

In the case of twin evaporator pumps, set the automatic start-up management pumps.

1. Enter technician password in the controller
2. Open the menu:
3. *Main Menu → View / Set Unit → Pumps → Evp Pmp Ctrl → Auto*

7.6 Alarm Limits

On the unit controller, enter the "Technician password" and set the alarm limits in the following menu:

Main Menu → Commission Unit → Alarm Limits




At the end of the Alarm Limits setting a restart of the controller ("Apply Changes") is required BEFORE to proceed with the startup of the unit.

7.7 Energy Meter


If the unit is provided with Opt.16/16a, proceed with the energy meter settings check.

Function of the buttons:



Access the setup menu


- 1) press "et" repeatedly until the page is displayed: "nEMo D4L "
- 2) Press and hold the "et" button until you see the page: "PASS "
- 3) Enter the password "1000" and confirm with the "et" key.



The "arrow" ▶ is used to move between the various digits, while ▲ ▼ is used to increment or decrement the numerical value of each digit. The ENTER key is used to confirm the password.


Depending on the wiring configuration, the respective programming scheme must be selected

- 1) log in with the password "1000 "
- 2) press the "et" button repeatedly until the page is displayed: "SYS "
- 3) Select the desired configuration: **3-2e** if the number of current transformers is 2, which is the standard configuration.




In case the energy meter is integrated in the modbus communication network of the POL687 controller of the chiller unit , the modbus parameters of the Nemo energy meter needs to be updated. It will be necessary to configure the address, transmission speed and parity bit on the energy meter corresponding to those on the chiller controller (POL 687).

- 1) log in with the password "1000 "
- 2) press "et " repeatedly until the page is displayed: "MDB Addr "
- 3) Select Address **20**
- 4) press "et " repeatedly until the page is displayed: "MDB BAud "
- 5) Select the baud rate **19200**
- 6) press "et " repeatedly until the page is displayed: "MDB par "
- 7) Select **None** Parity bit



Set the transformation ratio of the current transformers (CT ratio)

On the label of the CT it's indicated what the maximum primary and secondary currents are. For example max primary current 1250A / max secondary current 5A gives an CT ratio of 250 (1250/5)



Warning: the nominal current value at the Ime Nemo Energy meter input terminals should be between 1A~5A. Do not use CT's exceed this range in order to avoid damage to the energy meter!

7.8 Pre-Running Adjustments

Pre-Running Adjustments must be separately performed for each circuit



It is highly recommended to use a double sample sensor for the calibration of temperature sensors

7.8.1 Check and calibration of unit temperature sensors

Calibration of unit temperature sensors is a fundamental step for the correct operation of the unit.

There are three temperature sensors to be calibrated (for each circuit):

- Evaporator LWT
- Evaporator EWT
- OAT

7.8.1.1 Evaporator Leaving Water Temperature

- Place the sample and Evap LWT sensors in a container with ice
- Enter in *Commission Unit* → *Sensors Calibration* → *Unit* menu and then compare the Evap LWT value with that detected by the sample sensor
- If the temperature value measured by the unit sensor is different from the sample one, set the difference in the *Offset* parameter.



Make sure to have a good water/ice mix and wait for the water/ice system temperature to stabilize before to proceed with the calibration.

Place both sensors (sample and unit) in the middle of the container in order to not affect the readings.

7.8.1.2 Evaporator Entering Water Temperature

- Place the sample and Evap EWT sensors in a container with ice
- Enter in *Commission Unit* → *Calibrate Sensors* → *Unit* menu and then compare the Evap EWT value with that detected by the sample sensor
- If the temperature value measured by the unit sensor is different from the sample one, set the difference in the *Offset* parameter.



Make sure to have a good water/ice mix and wait for the water/ice system temperature to stabilize before to proceed with the calibration.

Place both sensors (sample and unit) in the middle of the container in order to not affect the readings.

7.8.1.3 Outside Air Temperature

- Place the sample and suction temperature sensors in ambient temperature
- Enter in *Commission Unit* → *Sensors Calibration* → *Unit* menu and then compare the OAT value with that detected by the sample sensor
- If the temperature value measured by the unit sensor is different from the sample one, set the difference in the *Offset* parameter.



Make sure to have a stable air conditions and wait until read unit and sample temperatures are stabilized respect to air ambient temperature before to proceed with the calibration.

7.8.2 Check and calibration of circuit temperature sensors

Calibration of circuit temperature sensors is a fundamental step for the correct operation of the unit.

There are two temperature sensors to be calibrated (for each circuit):

- The Suction temperature sensor (ST-1 & ST-2)
- The Discharge temperature sensor (DT-1 & DT-2)

7.8.2.1 Suction Temperature sensor

- Place the sample and suction temperature sensors in a container with ice
- Enter in *Commission Unit* → *Sensors Calibration* → *Circuit #1/2* menu and then compare the *Suction Tmp* value with that detected by the sample sensor
- If the temperature value measured by the unit sensor is different from the sample one, set the difference in the *Suction Offset* parameter.



Make sure to have a good water/ice mix and wait for the water/ice system temperature to stabilize before to proceed with the calibration.

Place both sensors (sample and unit) in the middle of the container in order to not affect the readings.



Suction temperature sensor is the most crucial of chiller's sensors as will guarantee the correct working of the EXV and consequent safe compressor running

7.8.2.2 Discharge temperature sensor

- Place the sample and discharge temperature sensors in ambient temperature
- Enter in *Commission Unit* → *Sensors Calibration* → *Circuit #1/2* menu and then compare the *Discharge Tmp* value with that detected by the sample sensor
- If the temperature value measured by the unit sensor is different from the sample one, set the difference in the *Disch Offset* parameter.



Make sure to have a stable air conditions and wait until read unit and sample temperatures are stabilized respect to air ambient temperature before to proceed with the calibration.

7.8.2.3 Economizer temperature

- Place the sample and Economizer temperature sensors in ambient temperature
- Enter in *Commission Unit* → *Calibrate Sensors* → *Circuit #1/2* menu and then compare the *Econ Temp* value with that detected by the sample sensor
- If the temperature value measured by the unit sensor is different from the sample one, set the difference in the *Eco Tmp Offset* parameter.



Make sure to have a stable air conditions and wait until read unit and sample temperatures are stabilized respect to air ambient temperature before to proceed with the calibration.

7.8.2.4 Liquid temperature

- Place the sample and Subcooling temperature sensors in ambient temperature
- Enter in *Commission Unit* → *Calibrate Sensors* → *Circuit #1/2* menu and then compare the *Liquid Temp* value with that detected by the sample sensor
- If the temperature value measured by the unit sensor is different from the sample one, set the difference in the *Liquid Tmp Offset* parameter.



Refer to Table A for the complete overview of the components positioning.

7.9 Dry Tests

Perform the Dry Tests by setting the unit in "test mode":

1. Enter the "Technician Password" on the controller
2. Go in *Main Menu* → *Unit Mode* → *Mode*
3. Set *Test*

All the dry tests are performable through the following menu:

7.9.1 Unit Alarm

Check the correct activation of the software general alarm:

Main Menu → Commission Unit → Manual Control → Unit → Unit Alarm

7.9.2 7.9.2 Pump #1/#2

Check the correct activation of the water pump (if it is controlled by the unit):

Main Menu → Commission Unit → Manual Control → Unit → Pump #1/#2 → set Pump Speed in %.

7.9.3 Circuit Alarm

Check the correct activation of the software general alarm:

Main Menu → Commission Unit → Manual Control → Circuit #1/2 → Circuit Alarm

7.9.4 Fan

Check the correct functionality of the fans:

Main Menu → Commission Unit → Manual Control → Circuit #1/2 → Fan speed

In this menu is possible choose the capacity of the fan. Moreover, during this phase check the rotation sense of the fans, if it is right the force of the air must be from the floor to the top.

7.9.5 Oil/VFD Heaters

Check the correct activation of compressor oil and VFD resistances:

Main Menu → Commission Unit → Manual Control → Circuit #1/2 → Oil Heater

Main Menu → Commission Unit → Manual Control → Circuit #1/2 → VFD Heater

7.9.6 7.9.6 VR Slides

Check the correct activation of the compressor VR slides:

Main Menu → Commission Unit → Manual Control → Circuit #1/2 → VRX

7.9.7 Expansion Valve

Verify the correct operation of the EXV valves:

Main Menu → Commission Unit → Manual Control → Circuit #1/2 → EXV Position

And set the opening percentage, it is possible verify the movement of the piston inside the expansion valve through the glass post on it.

7.9.8 Eco Expansion Valve

Verify the correct operation of the Eco EXV valves:

Main Menu → Commission Unit → Manual Control → Circuit #1/2 → EXV Position

And set the opening percentage, it is possible verify the movement of the piston inside the expansion valve through the glass post on it.

7.9.9 High Pressure Switches Test

Test the high-pressure switches by physically disconnecting them from the unit and by testing them until the intervention pressure by connecting them to a pressurized nitrogen cylinder.

7.9.10 Compressor addressing

Electrically disconnect the pressure transducer on the compressor (high or low) and check the activation of the related alarm on the correct circuit.

8 Start-Up

The first data acquisition for each circuit must be performed in "Cooling mode", in order to also check the correctness of the refrigerant charge by measuring the subcooling at the filter dryer (refer to E2.10 item of the *Commissioning Sheet*).



Make sure to open all the service valves before to perform the first unit Start-Up:

- *Liquid line*
- *Discharge line (if present)*
- *Suction line (if present)*
- *Turn on the water pump*

To do that, follow these steps, referring to the "Circuit #X":

1. Enter the "Technician Password" on the controller
2. Go in Main Menu → Unit Mode → Mode and set Cool
3. Go in Main Menu → Unit Enable
4. Set Circuit #1 → Enable, Circuit #2 → Disable
5. Set Unit → Enable
6. Set on Local the switch Q0

The circuit is now ready for the Running Adjustment (*paragraph 8.1*)

8.1 Running Adjustments

Running Adjustments must be separately performed for each circuit while it is running near the rating conditions.



Make sure that the circuit is working in cooling mode in stable conditions in order to don't affect the following operations result



Make sure that the circuit status is "Run: Normal" before to proceed with the Running Adjustments

8.1.1 Check and calibration of pressure transducers

Calibration of pressure transducers is a fundamental step for the correct operation of the unit.

There are two pressure sensors to be calibrated (for each circuit):

- The suction pressure transducers
- The discharge pressure transducers

8.1.1.1 Evaporator Pressure

- Connect the sample transducer to the "T shape" pressure port on which the suction pressure transducer is installed.
- With the unit on, with the *Suction Temperature* of $7^{\circ}\text{C} \pm 1^{\circ}\text{C}$ and before making gas charge adjustments, enter the *Commission Unit* → *Calibrate Sensors* → *Circuit #1/2* menu and then compare the *Evap Pressure* value with that detected by sample transducer
- If the pressure value measured by the unit transducer is different from the sample one, set the difference in the *Evap Pr Offset* parameter.



Sample transducer is the measuring device has been calibrated and it must be very accurate.



If this difference is greater than ± 100 kPa replace the transducer and repeat the operation.



Evaporator pressure transducer is the most crucial of chiller's transducer as will guarantee the correct working of the EXV with consequent safe compressor running and since all low-pressure safeties are based on its readings.

8.1.1.2 Condenser Pressure

- Connect the transducer to the "T shape" pressure port on which the discharge pressure transducer is installed.
- With the unit on, enter in *Commission Unit* → *Calibrate Sensors* → *Circuit #1/2* menu and then compare the *Cond Pressure* value with the one detected by the sample transducer. If the value of the pressure measured by the unit transducer is different from the sample one, set the difference in the *Cond Pr Offset* parameter.



If this difference is greater than ± 100 kPa replace the transducer and repeat the operation.

8.1.1.3 Oil Pressure

- Connect the sample transducer to the "T shape" pressure port on which the oil pressure transducer is installed.
- With the unit on, enter in *Commission Unit* → *Calibrate Sensors* → *Circuit #1/2* menu and then compare *Oil Pressure* value with *Condenser Pressure*.
- If the value of the pressure measured by the *Oil Pressure* transducer is different from the *Condenser Pressure*, set the difference in the *Oil PR Offset* parameter.



If this difference is greater than ± 100 kPa replace the transducer and repeat the operation.

8.1.2 Subcooling measurement point

The calculation of the subcooling at the filter dryer (in addition to the visual inspection of any flash gas on the liquid sight glass) is the main parameter by which the need for a charge adjustment is established. This quantity must be quantified with the least possible margin of error.

What's needed:

- Additional pressure transducer
- Additional temperature sensor

Proceed to the installation as follows:

- The pressure sensor must be installed on one of the two pressure points on the corner tap, close to the dryer filter.
- The temperature sensor must be installed on a smooth pipe section (not on a weld, for example), as close as possible to the pressure sensor mentioned above.



Temperature measurements are among the most difficult to perform. Install the temperature probes with a correct quantity of thermal paste, tighten the probes firmly to the pipe and abundantly insulate the probes so that external agents cannot affect the measurement.

- Subcooling (at the filter dryer) = $5^{\circ}\text{C} \pm 1^{\circ}\text{C}$
- Full liquid sight glass

If the Subcooling value is out of range, then proceed with the charge adjustment by using the recovery pump connected on the condenser outlet (before filter dryer).

The charge adjustment has to be performed step-by-step:

- For 50÷100kg circuits, proceed by adding/removing ±1kg of refrigerant at every step
- For 100÷500kg circuits, proceed by adding/removing ±2kg of refrigerant at every step



After every charge step, wait 5 minutes after the liquid temperature stabilizing before to proceed with the next eventual adjustment step.

8.2 Running Safeties Test

8.2.1 Flow Switches

With the running unit, disable the water pumps and check if “Water Flow Loss” alarm appears after 30sec. If not, check proceed with the check of correct flow switch installation and calibration.

8.3 Data acquisition



Make sure that the circuit is working in stable conditions to don't affect the Data Acquisition

- Data acquisition must be performed according the **Data Acquisition** section of the Commissioning Sheet.
- Data acquisition must be separately performed for each circuit in Chiller and Heat Pump mode. To select the circuit working mode refer to the following setting:

Start in Cool Mode:

Main Menu → Unit Mode → Cool

Enable this setpoint for testing the unit in Mechanical mode and through Unit Enable to select which Circuit to test.

- It is recommended to let the circuit reach the 100% of capacity before to proceed with the data acquisition (according to the plant load conditions).

To evaluate the stable operation of the unit check, following conditions must be satisfied:

- Circuit Status equal to “Run=Normal”
- ELWT and/or CLWT is as near as possible to the relative setpoint
- EXV is working in Superheat mode:
 - Main Menu → View/Set Circuit → EXV Cool/Heat → State = SSH
- SSH is equal to the SSH target for 5 minutes continuously:
 - Main Menu → View/Set Circuit → EXV Cool/Heat → SSH Target





***CLIMATIX Scope Light data recording during commissioning is strongly suggested.
For all material required for the recording get in contact with servicesupport@daikinapplied.eu***

9 TABLES


9.1 Unit Layout (Table A)


9.1.1 EWAD/H TZ-B and EWAD-MZB layout







9.1.2 EWAD TZ-C, EWAH TZ-C, EWAD-MZ-C layout








F4AL Compressor



F4AL Compressor



310240 Compressor



Sensor positioning is identical for all compressor models.

9.2 Unit configuration (Table B)

9.2.1 EWAD TZ-C, EWAH TZ-C

Unit configuration for EWAD TZC – Silver (ST, LN, XN)

| Daikin Model | Compressor | Motor | Inverter | Inverter Type | FANS TYPE ST - LN | FANS TYPE XN | FANS TYPE OP.142 (HA) | FANS TYPE OP.160 (100Pa) ST - LN | FANS TYPE OP.160 (100Pa) XN | FANS TYPE OP.161 (200Pa) | Fan C1 | Fan C2 | EXV | Eco EXV | EXV OP.187 (Water high temperature) |
|---------------|------------------------|-------|-----------|---------------|-------------------|--------------|-----------------------|----------------------------------|-----------------------------|--------------------------|--------|--------|---------|-------------------------|-------------------------------------|
| EWADH11TZS-C2 | 310240L VR 2.6 – 80 Hz | AC | AC 200 kW | DAE | AC900 | AC900L | AC900 | EC900 | AC900 | EC1400 | 10 | 12 | ETS 250 | Sporlan | ETS 400 |
| EWADH12TZS-C2 | 310240L VR 2.6 – 85 Hz | AC | AC 200 kW | DAE | AC900 | AC900L | AC900 | EC900 | AC900 | EC1400 | 10 | 12 | ETS 250 | Sporlan | ETS 400 |
| EWADH13TZS-C2 | 310240L VR 2.6 – 90 Hz | AC | AC 200 kW | DAE | AC900 | AC900L | AC900 | EC900 | AC900 | EC1400 | 12 | 12 | ETS 250 | Sporlan | ETS 400 |
| EWADC15TZS-C2 | F4AL VVR 55 Hz | AC | AC 330 kW | DAE | AC900 | AC900L | AC900 | EC900 | AC900 | EC1400 | 12 | 12 | ETS 250 | Sporlan | ETS 400 |
| EWADC16TZS-C2 | F4AL VVR 60 Hz | AC | AC 330 kW | DAE | AC900 | AC900L | AC900 | EC900 | AC900 | EC1400 | 12 | 14 | ETS 400 | Sporlan | ETS 400 |
| EWADH17TZS-C2 | F4AL VVR 65 Hz | AC | AC 400 kW | DAE | AC900 | AC900L | AC900 | EC900 | AC900 | EC1400 | 14 | 14 | ETS 400 | Sporlan | ETS 400 |
| EWADH18TZS-C2 | F4AL VVR 70 Hz | AC | AC 400 kW | DAE | AC900 | AC900L | AC900 | EC900 | AC900 | EC1400 | 14 | 16 | ETS 400 | Sporlan | ETS 400 |
| EWADH19TZS-C2 | F4AL VVR 75 Hz | AC | AC 400 kW | DAE | AC900 | AC900L | AC900 | EC900 | AC900 | EC1400 | 14 | 16 | ETS 400 | Sporlan | ETS 400 |

Unit configuration for EWAD TZC – Gold (ST, LN, XN)

| Daikin Model | Compressor | Motor | Inverter | Inverter Type | FANS TYPE ST | FANS TYPE XN | FANS TYPE OP.142 (HA) | FANS TYPE OP.160 (100Pa) | FANS TYPE OP.161 (200Pa) | Fan C1 | Fan C2 | EXV | Eco EXV | EXV OP.187 (Alta Temperatura Acqua) |
|---------------|------------------------|-------|-----------|---------------|--------------|--------------|-----------------------|--------------------------|--------------------------|--------|--------|---------|-------------------------|-------------------------------------|
| EWADC11TZX-C2 | 310240L VR 2.6 – 75 Hz | AC | AC 200 kW | DAE | AC900L | AC900L | EC900 | EC900 | EC1400 | 10 | 12 | ETS 250 | Sporlan | ETS 400 |
| EWADC12TZX-C2 | 310240L VR 2.6 – 80 Hz | AC | AC 200 kW | DAE | AC900L | AC900L | EC900 | EC900 | EC1400 | 12 | 12 | ETS 250 | Sporlan | ETS 400 |
| EWADH12TZX-C2 | 310240L VR 2.6 – 85 Hz | AC | AC 200 kW | DAE | AC900L | AC900L | EC900 | EC900 | EC1400 | 12 | 14 | ETS 250 | Sporlan | ETS 400 |
| EWADC14TZX-C2 | F4ALVVR 50 Hz | AC | AC 330 kW | DAE | AC900L | AC900L | EC900 | EC900 | EC1400 | 12 | 12 | ETS 400 | Sporlan | ETS 400 |
| EWADC15TZX-C2 | F4ALVVR 55 Hz | AC | AC 330 kW | DAE | AC900L | AC900L | EC900 | EC900 | EC1400 | 12 | 14 | ETS 400 | Sporlan | ETS 400 |
| EWADH16TZX-C2 | F4ALVVR 60 Hz | AC | AC 330 kW | DAE | AC900L | AC900L | EC900 | EC900 | EC1400 | 14 | 14 | ETS 400 | Sporlan | ETS 400 |
| EWADH17TZX-C2 | F4ALVVR 65 Hz | AC | AC 400 kW | DAE | AC900L | AC900L | EC900 | EC900 | EC1400 | 14 | 16 | ETS 400 | Sporlan | ETS 400 |

Unit configuration for EWAH TZC – Silver (ST, LN, XN)

| Daikin Model | Compressor | Motor | Inverter | Inverter Type | FANS TYPE ST - LN | FANS TYPE XN | FANS TYPE OP.142 (HA) | FANS TYPE OP.160 (100Pa) | FANS TYPE OP.161 (200Pa) | Fan C1 | Fan C2 | EXV | Eco EXV | EXV OP.187 (Alta Temperatura Acqua) |
|---------------|-------------------------|-------|-----------|---------------|-------------------|--------------|-----------------------|--------------------------|--------------------------|--------|--------|---------|-------------------------|-------------------------------------|
| EWAH710TZS-C2 | 310240S VR 2.6 – 80 Hz | AC | AC 200 kW | DAE | AC900 | AC900L | AC900 | EC900 | EC1400 | 6 | 8 | ETS 250 | Sporlan | ETS 400 |
| EWAH770TZS-C2 | 310240L VR 2.6 – 70 Hz | AC | AC 200 kW | DAE | AC900 | AC900L | AC900 | EC900 | EC1400 | 6 | 8 | ETS 250 | Sporlan | ETS 400 |
| EWAH880TZS-C2 | 310240L VR 2.6 – 80 Hz | AC | AC 200 kW | DAE | AC900 | AC900L | AC900 | EC900 | EC1400 | 8 | 8 | ETS 250 | Sporlan | ETS 400 |
| EWAH940TZS-C2 | 310240L VR 2.6 – 85 Hz | AC | AC 200 kW | DAE | AC900 | AC900L | AC900 | EC900 | EC1400 | 8 | 10 | ETS 250 | Sporlan | ETS 400 |
| EWAH990TZS-C2 | 310240L VR 2.6 – 90 Hz | AC | AC 200 kW | DAE | AC900 | AC900L | AC900 | EC900 | EC1400 | 10 | 10 | ETS 250 | Sporlan | ETS 400 |
| EWAH110TZS-C2 | 310240L VR 2.6 – 95 Hz | AC | AC 200 kW | DAE | AC900 | AC900L | AC900 | EC900 | EC1400 | 10 | 12 | ETS 250 | Sporlan | ETS 400 |
| EWAHC11TZS-C2 | 310240L VR 2.6 – 100 Hz | AC | AC 200 kW | DAE | AC900 | AC900L | AC900 | EC900 | EC1400 | 12 | 12 | ETS 250 | Sporlan | ETS 400 |
| EWAHC12TZS-C2 | 310240L VR 2.6 – 110 Hz | AC | AC 200 kW | DAE | AC900 | AC900L | AC900 | EC900 | EC1400 | 12 | 14 | ETS 250 | Sporlan | ETS 400 |
| EWAHC13TZS-C2 | F4AL VVR 65 Hz | AC | AC 330 kW | DAE | AC900 | AC900L | AC900 | EC900 | EC1400 | 12 | 12 | ETS 400 | Sporlan | ETS 400 |
| EWAHC14TZS-C2 | F4AL VVR 70 Hz | AC | AC 330 kW | DAE | AC900 | AC900L | AC900 | EC900 | EC1400 | 12 | 14 | ETS 400 | Sporlan | ETS 400 |
| EWAHC15TZS-C2 | F4AL VVR 75 Hz | AC | AC 330 kW | DAE | AC900 | AC900L | AC900 | EC900 | EC1400 | 14 | 14 | ETS 400 | Sporlan | ETS 400 |
| EWAHC16TZS-C2 | F4AL VVR 80 Hz | AC | AC 330 kW | DAE | AC900 | AC900L | AC900 | EC900 | EC1400 | 14 | 16 | ETS 400 | Sporlan | ETS 400 |

Unit configuration for EWAH TZC – Gold (ST, LN, XN)

| Daikin Model | Compressor | Motor | Inverter | Inverter Type | FANS TYPE ST | FANS TYPE XN | FANS TYPE OP.142 (HA) | FANS TYPE OP.160 (100Pa) | FANS TYPE OP.161 (200Pa) | Fan C1 | Fan C2 | EXV | Eco EXV | EXV OP.187 (Alta Temperatura Acqua) |
|---------------|-------------------------|-------|-----------|---------------|--------------|--------------|-----------------------|--------------------------|--------------------------|--------|--------|---------|-------------------------|-------------------------------------|
| EWAH670TZX-C2 | 310240L VR 2.6 – 60 Hz | AC | AC 200 kW | DAE | AC900L | AC900L | EC900 | EC900 | EC1400 | 6 | 8 | ETS 250 | Sporlan | ETS 400 |
| EWAH780TZX-C2 | 310240L VR 2.6 – 70 Hz | AC | AC 200 kW | DAE | AC900L | AC900L | EC900 | EC900 | EC1400 | 8 | 8 | ETS 250 | Sporlan | ETS 400 |
| EWAH840TZX-C2 | 310240L VR 2.6 – 75 Hz | AC | AC 200 kW | DAE | AC900L | AC900L | EC900 | EC900 | EC1400 | 8 | 10 | ETS 250 | Sporlan | ETS 400 |
| EWAH950TZX-C2 | 310240L VR 2.6 – 85 Hz | AC | AC 200 kW | DAE | AC900L | AC900L | EC900 | EC900 | EC1400 | 10 | 12 | ETS 250 | Sporlan | ETS 400 |
| EWAHC10TZX-C2 | 310240L VR 2.6 – 90 Hz | AC | AC 200 kW | DAE | AC900L | AC900L | EC900 | EC900 | EC1400 | 12 | 12 | ETS 250 | Sporlan | ETS 400 |
| EWAHC11TZX-C2 | 310240L VR 2.6 – 100 Hz | AC | AC 200 kW | DAE | AC900L | AC900L | EC900 | EC900 | EC1400 | 12 | 14 | ETS 250 | Sporlan | ETS 400 |
| EWAHC12TZX-C2 | F4ALVVR 60 Hz | AC | AC 200 kW | DAE | AC900 | AC900L | EC900 | EC900 | EC1400 | 12 | 12 | ETS 400 | Sporlan | ETS 400 |
| EWAHC13TZX-C2 | F4ALVVR 65 Hz | AC | AC 330 kW | DAE | AC900 | AC900L | EC900 | EC900 | EC1400 | 12 | 14 | ETS 400 | Sporlan | ETS 400 |
| EWAHC14TZX-C2 | F4ALVVR 70 Hz | AC | AC 330 kW | DAE | AC900 | AC900L | EC900 | EC900 | EC1400 | 14 | 14 | ETS 400 | Sporlan | ETS 400 |
| EWAHC15TZX-C2 | F4ALVVR 75 Hz | AC | AC 330 kW | DAE | AC900 | AC900L | EC900 | EC900 | EC1400 | 14 | 16 | ETS 400 | Sporlan | ETS 400 |

9.2.2 EWAD MZ-C

Unit configuration for EWAD MZC – Silver

| Daikin Model | Compressor | Motor | Inverter | Inverter Type | FANS TYPE | FANS TYPE OP.142 (HA) | FANS TYPE OP.160 (100Pa) | FANS TYPE OP.161 (200Pa) | Fan C1 | Fan C2 | EXV | Eco EXV | EXV OP.187 (Alta Temperatura Acqua) |
|---------------|------------------------|-------|-----------|---------------|-----------|-----------------------|--------------------------|--------------------------|--------|--------|---------|-------------------------|-------------------------------------|
| EWADH10MZSSC2 | 310240L VR 2.6 – 80 Hz | AC | AC 200 kW | DAE | AC900 | AC900 | EC900 | EC1400 | 10 | 12 | ETS 250 | Sporlan | ETS 400 |
| EWADC11MZSSC2 | 310240L VR 2.6 – 85 Hz | AC | AC 200 kW | DAE | AC900 | AC900 | EC900 | EC1400 | 10 | 12 | ETS 250 | Sporlan | ETS 400 |
| EWADH11MZSSC2 | 310240L VR 2.6 – 90 Hz | AC | AC 200 kW | DAE | AC900 | AC900 | EC900 | EC1400 | 12 | 12 | ETS 250 | Sporlan | ETS 400 |
| EWADC13MZSSC2 | F4ALVVR 55 Hz | AC | AC 330 kW | DAE | AC900 | AC900 | EC900 | EC1400 | 12 | 12 | ETS 400 | Sporlan | ETS 400 |
| EWADC14MZSSC2 | F4ALVVR 60 Hz | AC | AC 330 kW | DAE | AC900 | AC900 | EC900 | EC1400 | 12 | 14 | ETS 400 | Sporlan | ETS 400 |
| EWADC15MZSSC2 | F4ALVVR 65 Hz | AC | AC 400 kW | DAE | AC900 | AC900 | EC900 | EC1400 | 14 | 14 | ETS 400 | Sporlan | ETS 400 |
| EWADC16MZSSC2 | F4ALVVR 70 Hz | AC | AC 400 kW | DAE | AC900 | AC900 | EC900 | EC1400 | 14 | 16 | ETS 400 | Sporlan | ETS 400 |

Unit configuration for EWAD MZC – Gold

| Daikin model | Compressor | Motor | Inverter | Inverter Type | FANS TYPE | FANS TYPE OP.142 (HA) | FANS TYPE OP.160 (100Pa) | FANS TYPE OP.161 (200Pa) | Fan C1 | Fan C2 | EXV | Eco EXV | EXV OP.187 (Alta Temperatura Acqua) |
|--------------|------------------------|-------|-----------|---------------|-----------|-----------------------|--------------------------|--------------------------|--------|--------|---------|-------------------------|-------------------------------------|
| EWADC10MXSC2 | 310240L VR 2.6 – 75 Hz | AC | AC 200 kW | DAE | AC900 | AC900 | EC900 | EC1400 | 10 | 12 | ETS 250 | Sporlan | ETS 400 |
| EWADH10MXSC2 | 310240L VR 2.6 – 80 Hz | AC | AC 200 kW | DAE | AC900 | AC900 | EC900 | EC1400 | 12 | 12 | ETS 250 | Sporlan | ETS 400 |
| EWADH11MXSC2 | 310240L VR 2.6 – 85 Hz | AC | AC 200 kW | DAE | AC900 | AC900 | EC900 | EC1400 | 12 | 14 | ETS 250 | Sporlan | ETS 400 |
| EWADC12MXSC2 | F4AL VVR 50 Hz | AC | AC 330 kW | DAE | AC900 | AC900 | EC900 | EC1400 | 12 | 12 | ETS 400 | Sporlan | ETS 400 |
| EWADC13MXSC2 | F4AL VVR 55 Hz | AC | AC 330 kW | DAE | AC900 | AC900 | EC900 | EC1400 | 12 | 14 | ETS 400 | Sporlan | ETS 400 |
| EWADC14MXSC2 | F4AL VVR 60 Hz | AC | AC 330 kW | DAE | AC900 | AC900 | EC900 | EC1400 | 14 | 14 | ETS 400 | Sporlan | ETS 400 |
| EWADC15MXSC2 | F4AL VVR 65 Hz | AC | AC 400 kW | DAE | AC900 | AC900 | EC900 | EC1400 | 14 | 16 | ETS 400 | Sporlan | ETS 400 |

Unit configuration for EWAD MZC – Platinum

| Daikin Model | Compressor | Motor | Inverter | Inverter Type | FANS TYPE | FANS TYPE OP.142 (HA) | FANS TYPE OP.160 (100Pa) | FANS TYPE OP.161 (200Pa) | Fan C1 | Fan C2 | EXV | Eco EXV | EXV OP.187 (Alta Temperatura Acqua) |
|---------------|------------------------|-------|-----------|---------------|-----------|-----------------------|--------------------------|--------------------------|--------|--------|---------|-------------------------|-------------------------------------|
| EWADC10MZPSC2 | 310240L VR 2.6 – 75 Hz | AC | AC 200 kW | DAE | EC900 | EC900 | EC900 | EC1400 | 10 | 12 | ETS 250 | Sporlan | ETS 400 |
| EWADH10MZPSC2 | 310240L VR 2.6 – 80 Hz | AC | AC 200 kW | DAE | EC900 | EC900 | EC900 | EC1400 | 12 | 12 | ETS 250 | Sporlan | ETS 400 |
| EWADH11MZPSC2 | 310240L VR 2.6 – 85 Hz | AC | AC 200 kW | DAE | EC900 | EC900 | EC900 | EC1400 | 12 | 14 | ETS 250 | Sporlan | ETS 400 |
| EWADC12MZPSC2 | F4AL VVR 50 Hz | AC | AC 330 kW | DAE | EC900 | EC900 | EC900 | EC1400 | 12 | 12 | ETS 400 | Sporlan | ETS 400 |
| EWADC13MZPSC2 | F4AL VVR 55 Hz | AC | AC 330 kW | DAE | EC900 | EC900 | EC900 | EC1400 | 12 | 14 | ETS 400 | Sporlan | ETS 400 |
| EWADC14MZPSC2 | F4AL VVR 60 Hz | AC | AC 330 kW | DAE | EC900 | EC900 | EC900 | EC1400 | 14 | 14 | ETS 400 | Sporlan | ETS 400 |
| EWADC15MZPSC2 | F4AL VVR 65 Hz | AC | AC 400 kW | DAE | EC900 | EC900 | EC900 | EC1400 | 14 | 16 | ETS 400 | Sporlan | ETS 400 |

9.2.3 EWAD TZ-B and EWAH TZ-B

| Modello Daikin | Modello McQuay | Compressore | Inv | Fan 50Hz | Fan 60 Hz | Fan Brine 50/60 Hz | Fan HA 50/60 Hz | Op. 158/159 Fan BR5 | Opt.160 SS-SL-SR 50/60 Hz | Fan Opt.161 SS-SL-SR 50/60 Hz | EXV | FanC1 | FanC2 |
|----------------|----------------|--------------|-----|----------|-----------|--------------------|-----------------|---------------------|---------------------------|-------------------------------|--------|-------|-------|
| EWAD160TZS B1 | ATS 050.1 B SE | 3120-60Hz-AC | 90 | AC700 | AC900 | AC900L | AC900 | DC1000-700 | AC900 | EC1400 | ETS100 | 4 | - |
| EWAD190TZS B1 | ATS 060.1 B SE | 3120-70Hz-AC | 90 | AC700 | AC900 | AC900L | AC900 | DC1000-700 | AC900 | EC1400 | ETS100 | 4 | - |
| EWAD240TZS B1 | ATS 070.1 B SE | 3122-60Hz-AC | 90 | AC700 | AC900 | AC900L | AC900 | DC1000-700 | AC900 | EC1400 | ETS250 | 4 | - |
| EWAD270TZS B1 | ATS 080.1 B SE | 3122-70Hz-AC | 90 | AC700 | AC900 | AC900L | AC900 | DC1000-700 | AC900 | EC1400 | ETS250 | 6 | - |
| EWAD300TZS B1 | ATS 090.1 B SE | 3122-80Hz-AC | 120 | AC700 | AC900 | AC900L | AC900 | DC1000-700 | AC900 | EC1400 | ETS250 | 6 | - |
| EWAD360TZS B1 | ATS 100.1 B SE | 3122-90Hz-AC | 120 | AC700 | AC900 | AC900L | AC900 | DC1000-700 | AC900 | EC1400 | ETS250 | 8 | - |
| EWAD380TZS B2 | ATS 120.2 B SE | 3120-70Hz-AC | 90 | AC700 | AC900 | AC900L | AC900 | DC1000-700 | AC900 | EC1400 | ETS100 | 4 | 4 |
| EWAD450TZS B2 | ATS 130.2 B SE | 3122-60Hz-AC | 90 | AC700 | AC900 | AC900L | AC900 | DC1000-700 | AC900 | EC1400 | ETS250 | 4 | 4 |
| EWAD495TZS B2 | ATS 150.2 B SE | 3122-65Hz-AC | 90 | AC700 | AC900 | AC900L | AC900 | DC1000-700 | AC900 | EC1400 | ETS250 | 4 | 6 |
| EWAD570TZS B2 | ATS 170.2 B SE | 3122-75Hz-AC | 120 | AC700 | AC900 | AC900L | AC900 | DC1000-700 | AC900 | EC1400 | ETS250 | 6 | 6 |
| EWAD610TZS B2 | ATS 180.2 B SE | 3122-80Hz-AC | 120 | AC700 | AC900 | AC900L | AC900 | DC1000-700 | AC900 | EC1400 | ETS250 | 6 | 6 |
| EWAD660TZS B2 | ATS 200.2 B SE | 3122-85Hz-AC | 120 | AC700 | AC900 | AC900L | AC900 | DC1000-700 | AC900 | EC1400 | ETS250 | 6 | 6 |
| EWAD700TZS B2 | ATS 210.2 B SE | 3122-90Hz-AC | 120 | AC700 | AC900 | AC900L | AC900 | DC1000-700 | AC900 | EC1400 | ETS250 | 6 | 8 |

| Modello Daikin | Modello McQuay | Compressor | Inv | Fan 50/60 Hz | Fan Brine 50/60Hz | Fan HA 50/60 Hz | Op. 158/159 Fan BRS | Fan Opt.160 SS-SL 50/60 Hz | Fan Opt.161 SS-SL 50/60 Hz | EXV | FanC1 | FanC2 |
|----------------|----------------|--------------|-------|--------------|-------------------|-----------------|---------------------|----------------------------|----------------------------|--------|-------|-------|
| EWAD820T2S B2 | ATS 230.2 B SE | F3AS-70Hz-AC | 200kW | AC900 | AC900 | AC900 | DC1000L | EC900 | EC1400 | ETS250 | 6 | 8 |
| EWAD900T2S B2 | ATS 260.2 B SE | F3AL-70Hz-AC | 200kW | AC900 | AC900 | AC900 | DC1000L | EC900 | EC1400 | ETS250 | 6 | 8 |
| EWAD990T2S B2 | ATS 280.2 B SE | F3AL-75Hz-AC | 200kW | AC900 | AC900 | AC900 | DC1000L | EC900 | EC1400 | ETS250 | 8 | 8 |
| EWADC10T2S B2 | ATS 290.2 B SE | F3AL-80Hz-AC | 200kW | AC900 | AC900 | AC900 | DC1000L | EC900 | EC1400 | ETS250 | 8 | 10 |
| EWADC11T2S B2 | ATS 310.2 B SE | F3AL-85Hz-AC | 200kW | AC900 | AC900 | AC900 | DC1000L | EC900 | EC1400 | ETS250 | 10 | 10 |

| Modello Daikin | Modello McQuay | Compressore | Inverter | Fan50Hz | Fan60Hz | Fan Brine 50/60 Hz | Fan HA 50/60 Hz | OP. 158/159 Fan BRS | Fan Opt.160 50/60 Hz | Fan Opt.161 50/60 Hz | EXV | FanC1 | FanC2 |
|----------------|----------------|--------------|----------|---------|---------|--------------------|-----------------|---------------------|----------------------|----------------------|--------|-------|-------|
| EWAD820T2SRB2 | ATS 230.2 B SE | F3AS-70Hz-AC | 200kW | AC700 | AC900 | AC900L | AC900 | DC1000-700 | AC900 | EC1400 | ETS250 | 8 | 8 |
| EWAD900T2SRB2 | ATS 260.2 B SE | F3AL-70Hz-AC | 200kW | AC700 | AC900 | AC900L | AC900 | DC1000-700 | AC900 | EC1400 | ETS250 | 8 | 8 |
| EWAD990T2SRB2 | ATS 280.2 B SE | F3AL-75Hz-AC | 200kW | AC700 | AC900 | AC900L | AC900 | DC1000-700 | AC900 | EC1400 | ETS250 | 8 | 10 |
| EWADC10T2SRB2 | ATS 290.2 B SE | F3AL-80Hz-AC | 200kW | AC700 | AC900 | AC900L | AC900 | DC1000-700 | AC900 | EC1400 | ETS250 | 10 | 10 |
| EWADC11T2SRB2 | ATS 310.2 B SE | F3AL-85Hz-AC | 200kW | AC700 | AC900 | AC900L | AC900 | DC1000-700 | AC900 | EC1400 | ETS250 | 10 | 12 |

| Modello Daikin | Modello McQuay | Compressore | Inverter | Fan 50/60 Hz | Fan Brine 50/60 Hz | Fan Opt.160 50/60 Hz | Fan Opt.161 50/60 Hz | Fan HA 50/60 Hz | OP. 158/159 Fan BRS | EXV | FanC1 | FanC2 |
|----------------|----------------|----------------|----------|--------------|--------------------|----------------------|----------------------|-----------------|---------------------|--------|-------|-------|
| EWAD190TZX B1 | ATS 050.1 B XE | 3120-60Hz-DC | 90kW | AC700 | AC900L | AC900 | EC1400 | DC1000L | DC1000-700 | ETS100 | 6 | - |
| EWAD220TZX B1 | ATS 060.1 B XE | 3120-70Hz-DC | 90kW | AC700 | AC900L | AC900 | EC1400 | DC1000L | DC1000-700 | ETS100 | 6 | - |
| EWAD240TZX B1 | ATS 070.1 B XE | 3122-60Hz-DC | 120kW | AC700 | AC900L | AC900 | EC1400 | DC1000L | DC1000-700 | ETS250 | 6 | - |
| EWAD290TZX B1 | ATS 080.1 B XE | 3122-70Hz-DC | 120kW | AC700 | AC900L | AC900 | EC1400 | DC1000L | DC1000-700 | ETS250 | 8 | - |
| EWAD320TZX B1 | ATS 090.1 B XE | 3122-80Hz-DC | 120kW | AC700 | AC900L | AC900 | EC1400 | DC1000L | DC1000-700 | ETS250 | 8 | - |
| EWAD360TZX B2 | ATS 110.2 B XE | 3120-60Hz-DC | 90kW | AC700 | AC900L | AC900 | EC1400 | DC1000L | DC1000-700 | ETS100 | 4 | 6 |
| EWAD420TZX B2 | ATS 120.2 B XE | 3120-70Hz-DC | 90kW | AC700 | AC900L | AC900 | EC1400 | DC1000L | DC1000-700 | ETS100 | 4 | 6 |
| EWAD450TZX B2 | ATS 140.2 B XE | 3122-60Hz-DC | 120kW | AC700 | AC900L | AC900 | EC1400 | DC1000L | DC1000-700 | ETS250 | 6 | 6 |
| EWAD540TZX B2 | ATS 150.2 B XE | 3122-65Hz-DC | 120kW | AC700 | AC900L | AC900 | EC1400 | DC1000L | DC1000-700 | ETS250 | 6 | 6 |
| EWAD570TZX B2 | ATS 160.2 B XE | 3122-70Hz-DC | 120kW | AC700 | AC900L | AC900 | EC1400 | DC1000L | DC1000-700 | ETS250 | 6 | 6 |
| EWAD610TZX B2 | ATS 170.2 B XE | 3122-75Hz-DC | 120kW | AC700 | AC900L | AC900 | EC1400 | DC1000L | DC1000-700 | ETS250 | 6 | 8 |
| EWAD660TZX B2 | ATS 180.2 B XE | 3122-80Hz-DC | 120kW | AC700 | AC900L | AC900 | EC1400 | DC1000L | DC1000-700 | ETS250 | 8 | 8 |
| EWAD680TZX B2 | ATS 190.2 B XE | 3122-85Hz-DC | 120kW | AC700 | AC900L | AC900 | EC1400 | DC1000L | DC1000-700 | ETS250 | 8 | 8 |
| EWAD770TZX B2 | ATS 220.2 B XE | F3AS-67.5Hz-DC | 200kW | AC700 | AC900L | AC900 | EC1400 | DC1000L | DC1000-700 | ETS250 | 8 | 8 |
| EWAD850TZX B2 | ATS 240.2 B XE | F3AS-75Hz-DC | 200kW | AC700 | AC900L | AC900 | EC1400 | DC1000L | DC1000-700 | ETS250 | 8 | 8 |
| EWAD910TZX B2 | ATS 260.2 B XE | F3AL-70Hz-DC | 200kW | AC700 | AC900L | AC900 | EC1400 | DC1000L | DC1000-700 | ETS250 | 8 | 10 |
| EWADC10TZX B2 | ATS 290.2 B XE | F3AL-75Hz-DC | 200kW | AC700 | AC900L | AC900 | EC1400 | DC1000L | DC1000-700 | ETS250 | 10 | 10 |
| EWADC11TZX B2 | ATS 310.2 B XE | F3AL-80Hz-DC | 200kW | AC700 | AC900L | AC900 | EC1400 | DC1000L | DC1000-700 | ETS250 | 10 | 12 |

| Modello Daikin | Modello McQuay | Compressore | Inverter | Fan 50/60 Hz | Fan Brine 50/60 Hz | Fan HA 50/60 Hz | OP. 158/159 Fan BRS | Fan Opt.160 50/60 Hz | Fan Opt.161 50/60 Hz | EXV | FanC1 | FanC2 |
|----------------|----------------|--------------|----------|--------------|--------------------|-----------------|---------------------|----------------------|----------------------|--------|-------|-------|
| EWAD190TZP B1 | ATS 050.1 B PR | 3120-60Hz-DC | 90kW | DC1000-700 | DC1000-700 | DC1000L | STD | EC900 | EC1400 | ETS100 | 8 | - |
| EWAD220TZP B1 | ATS 060.1 B PR | 3120-70Hz-DC | 90kW | DC1000-700 | DC1000-700 | DC1000L | STD | EC900 | EC1400 | ETS100 | 8 | - |
| EWAD240TZP B1 | ATS 070.1 B PR | 3122-60Hz-DC | 120kW | DC1000-700 | DC1000-700 | DC1000L | STD | EC900 | EC1400 | ETS250 | 8 | - |
| EWAD290TZP B1 | ATS 080.1 B PR | 3122-70Hz-DC | 120kW | DC1000-700 | DC1000-700 | DC1000L | STD | EC900 | EC1400 | ETS250 | 8 | - |
| EWAD300TZP B1 | ATS 090.1 B PR | 3122-80Hz-DC | 120kW | DC1000-700 | DC1000-700 | DC1000L | STD | EC900 | EC1400 | ETS250 | 10 | - |
| EWAD350TZP B2 | ATS 100.2 B PR | 3120-60Hz-DC | 90kW | DC1000-700 | DC1000-700 | DC1000L | STD | EC900 | EC1400 | ETS100 | 6 | 6 |
| EWAD420TZP B2 | ATS 120.2 B PR | 3120-70Hz-DC | 90kW | DC1000-700 | DC1000-700 | DC1000L | STD | EC900 | EC1400 | ETS100 | 6 | 8 |
| EWAD495TZP B2 | ATS 140.2 B PR | 3122-60Hz-DC | 120kW | DC1000-700 | DC1000-700 | DC1000L | STD | EC900 | EC1400 | ETS250 | 8 | 8 |
| EWAD550TZP B2 | ATS 160.2 B PR | 3122-65Hz-DC | 120kW | DC1000-700 | DC1000-700 | DC1000L | STD | EC900 | EC1400 | ETS250 | 8 | 10 |
| EWAD620TZP B2 | ATS 180.2 B PR | 3122-75Hz-DC | 120kW | DC1000-700 | DC1000-700 | DC1000L | STD | EC900 | EC1400 | ETS250 | 10 | 10 |
| EWAD720TZP B2 | ATS 210.2 B PR | F3AS-60Hz-DC | 200kW | DC1000-700 | DC1000-700 | DC1000L | STD | EC900 | EC1400 | ETS250 | 10 | 10 |
| EWAD820TZP B2 | ATS 230.2 B PR | F3AS-70Hz-DC | 200kW | DC1000-700 | DC1000-700 | DC1000L | STD | EC900 | EC1400 | ETS250 | 10 | 12 |
| EWAD950TZP B2 | ATS 270.2 B PR | F3AL-70Hz-DC | 200kW | DC1000-700 | DC1000-700 | DC1000L | STD | EC900 | EC1400 | ETS250 | 12 | 12 |

| Modello Daikin | Comp | Hz | Inverter | Fan C1 | Fan C2 | Fan | Fan Brine | Fan HA | OP. 158/159 Fan BRS | Fan Opt. 160 | Fan Opt. 161 |
|----------------|---------|----|----------|--------|--------|-------|-----------|--------|---------------------|--------------|--------------|
| EWAH170TZS-B1 | 3122 AC | 60 | 90 kW | 4 | 0 | AC700 | AC900L | AC900 | DC1000-700 | AC900 | EC1400 |
| EWAH200TZS-B1 | 3122 AC | 70 | 90 kW | 4 | 0 | AC700 | AC900L | AC900 | DC1000-700 | AC900 | EC1400 |
| EWAH240TZS-B1 | 3122 AC | 85 | 120 kW | 6 | 0 | AC700 | AC900L | AC900 | DC1000-700 | AC900 | EC1400 |
| EWAH290TZS-B1 | F3AS AC | 75 | 200 kW | 6 | 0 | AC700 | AC900L | AC900 | DC1000-700 | AC900 | EC1400 |
| EWAH330TZS-B1 | F3AL AC | 75 | 200 kW | 6 | 0 | AC700 | AC900L | AC900 | DC1000-700 | AC900 | EC1400 |
| EWAH390TZS-B2 | 3122 AC | 70 | 90 kW | 4 | 6 | AC700 | AC900L | AC900 | DC1000-700 | AC900 | EC1400 |
| EWAH420TZS-B2 | 3122 AC | 75 | 120 kW | 4 | 6 | AC700 | AC900L | AC900 | DC1000-700 | AC900 | EC1400 |
| EWAH490TZS-B2 | 3122 AC | 85 | 120 kW | 6 | 6 | AC700 | AC900L | AC900 | DC1000-700 | AC900 | EC1400 |
| EWAH530TZS-B2 | 3122 AC | 90 | 120 kW | 6 | 6 | AC700 | AC900L | AC900 | DC1000-700 | AC900 | EC1400 |
| EWAH600TZS-B2 | F3AS AC | 80 | 200 kW | 6 | 6 | AC700 | AC900L | AC900 | DC1000-700 | AC900 | EC1400 |
| EWAH690TZS-B2 | F3AL AC | 80 | 200 kW | 6 | 8 | AC700 | | | | | |
| EWAH750TZS-B2 | F3AL AC | 86 | 200 kW | 8 | 8 | AC700 | | | | | |
| EWAH820TZS-B2 | F3BL AC | 65 | 330 kW | 8 | 8 | AC700 | | | | | |
| EWAH920TZS-B2 | F3BL AC | 75 | 330 kW | 8 | 10 | AC700 | | | | | |
| EWAH980TZS-B2 | F3BL AC | 80 | 330 kW | 10 | 10 | AC700 | | | | | |
| EWAHC10TZS-B2 | F3BL AC | 85 | 330 kW | 10 | 10 | AC700 | | | | | |

| Modello Daikin | Comp | Hz | Inverter | Fan C1 | Fan C2 | Fan | Fan Brine | Fan HA | OP. 158/159 Fan BRS | Fan Opt.160 | Fan Opt.161 |
|----------------|---------|----|----------|--------|--------|-------|-----------|---------|---------------------|-------------|-------------|
| EWAH180TZX-B1 | 3122 AC | 60 | 90 kW | 6 | 0 | AC700 | AC900L | DC1000L | DC1000-700 | AC900 | EC1400 |
| EWAH220TZX-B1 | 3122 AC | 75 | 120 kW | 8 | 0 | AC700 | AC900L | DC1000L | DC1000-700 | AC900 | EC1400 |
| EWAH270TZX-B1 | F3AS AC | 65 | 200 kW | 6 | 0 | AC700 | AC900L | DC1000L | DC1000-700 | AC900 | EC1400 |
| EWAH300TZX-B1 | F3AS AC | 75 | 200 kW | 8 | 0 | AC700 | AC900L | DC1000L | DC1000-700 | AC900 | EC1400 |
| EWAH350TZX-B2 | 3122 AC | 60 | 90 kW | 6 | 6 | AC700 | AC900L | DC1000L | DC1000-700 | AC900 | EC1400 |
| EWAH390TZX-B2 | 3122 AC | 65 | 90 kW | 6 | 6 | AC700 | AC900L | DC1000L | DC1000-700 | AC900 | EC1400 |
| EWAH430TZX-B2 | 3122 AC | 70 | 90 kW | 6 | 8 | AC700 | AC900L | DC1000L | DC1000-700 | AC900 | EC1400 |
| EWAH480TZX-B2 | 3122 AC | 80 | 120 kW | 8 | 8 | AC700 | AC900L | DC1000L | DC1000-700 | AC900 | EC1400 |
| EWAH580TZX-B2 | F3AS AC | 68 | 200 kW | 6 | 8 | AC700 | AC900L | DC1000L | DC1000-700 | AC900 | EC1400 |
| EWAH620TZX-B2 | F3AS AC | 75 | 200 kW | 8 | 8 | AC700 | AC900L | DC1000L | DC1000-700 | AC900 | EC1400 |
| EWAH670TZX-B2 | F3AL AC | 70 | 200 kW | 8 | 8 | AC700 | | | | | |
| EWAH710TZX-B2 | F3AL AC | 75 | 200 kW | 8 | 10 | AC700 | | | | | |
| EWAH760TZX-B2 | F3AL AC | 80 | 200 kW | 10 | 10 | AC700 | | | | | |
| EWAH820TZX-B2 | F3BL AC | 60 | 330 kW | 10 | 12 | AC700 | | | | | |
| EWAH930TZX-B2 | F3BL AC | 68 | 330 kW | 12 | 12 | AC700 | | | | | |
| EWAH990TZX-B2 | F3BL AC | 75 | 330 kW | 12 | 12 | AC700 | | | | | |

| Modello Daikin | Comp | Hz | Inverter | Fan C1 | Fan C2 | Fan PS-PL-PR | Fan Brine | Fan HA | OP. 158/159 Fan BRS | Fan Opt. 160 | Fan Opt. 161 |
|----------------|---------|----|----------|--------|--------|--------------|------------|---------|---------------------------|--------------|--------------|
| EWAH370TZP-B2 | 3122 DC | 60 | 90 kW | 8 | 8 | DC1000-700 | DC1000-700 | DC1000L | STD | EC900 | EC1400 |
| EWAH440TZP-B2 | 3122 DC | 70 | 90 kW | 10 | 10 | DC1000-700 | DC1000-700 | DC1000L | STD | EC900 | EC1400 |
| EWAH530TZP-B2 | F3AS DC | 60 | 200 kW | 8 | 8 | DC1000-700 | DC1000-700 | DC1000L | STD | EC900 | EC1400 |
| EWAH610TZP-B2 | F3AS DC | 70 | 200 kW | 8 | 10 | DC1000-700 | DC1000-700 | DC1000L | STD | EC900 | EC1400 |
| EWAH690TZP-B2 | F3AL DC | 70 | 200 kW | 10 | 12 | DC1000-700 | | | | | |
| EWAH770TZP-B2 | F3BL DC | 55 | 330 kW | 12 | 12 | DC1000-700 | | | | | |

9.2.4 EWAD MZ-B

| Modello Daikin | Compressore | Opt. 260 Boost Comp | Inverter | Fan 50/60Hz | Fan Brine 50/60Hz | Fan HA 50/60 Hz | Fan Opt. 158 | EXV | FanC1 | FanC2 |
|-----------------|--------------|---------------------------|----------|----------------|----------------------|-----------------------|-----------------|--------|-------|-------|
| EWAD380MZ-SS B2 | 3120-70Hz-AC | NA | 90kW | AC900 | AC900 | AC900 | DC1000L | ETS100 | 4 | 4 |
| EWAD450MZ-SS B2 | 3122-60Hz-AC | NA | 90kW | AC900 | AC900 | AC900 | DC1000L | ETS250 | 4 | 4 |
| EWAD495MZ-SS B2 | 3122-65Hz-AC | NA | 90kW | AC900 | AC900 | AC900 | DC1000L | ETS250 | 4 | 6 |
| EWAD570MZ-SS B2 | 3122-75Hz-AC | 90 Hz | 120kW | AC900 | AC900 | AC900 | DC1000L | ETS250 | 6 | 6 |
| EWAD610MZ-SS B2 | 3122-80Hz-AC | NA | 120kW | AC900 | AC900 | AC900 | DC1000L | ETS250 | 6 | 6 |
| EWAD660MZ-SS B2 | 3122-85Hz-AC | NA | 120kW | AC900 | AC900 | AC900 | DC1000L | ETS250 | 6 | 6 |
| EWAD700MZ-SS B2 | 3122-90Hz-AC | NA | 120kW | AC900 | AC900 | AC900 | DC1000L | ETS250 | 6 | 8 |
| EWAD820MZ-SS B2 | F3AS-70Hz-AC | 80 Hz | 200kW | AC900 | AC900 | AC900 | DC1000L | ETS250 | 6 | 8 |
| EWAD900MZ-SS B2 | F3AL-70Hz-AC | NA | 200kW | AC900 | AC900 | AC900 | DC1000L | ETS250 | 6 | 8 |
| EWADC10MZ-SS B2 | F3AL-75Hz-AC | NA | 200kW | AC900 | AC900 | AC900 | DC1000L | ETS250 | 8 | 8 |
| EWADH10MZ-SS B2 | F3AL-75Hz-AC | 85 Hz | 200kW | AC900 | AC900 | AC900 | DC1000L | ETS250 | 8 | 10 |
| EWADH11MZ-SS B2 | F3AL-85Hz-AC | NA | 200kW | AC900 | AC900 | AC900 | DC1000L | ETS250 | 10 | 12 |

| Modello Daikin | Compressore | Opt. 260 Boost Comp | Inverter | Fan 50/60 Hz | Fan Brine 50/60Hz | Fan HA 50/60 Hz | EXV | FanC1 | FanC2 |
|-----------------|----------------|---------------------------|----------|-----------------|----------------------|-----------------------|--------|-------|-------|
| EWAD360MZ-XS B2 | 3120-60Hz-DC | NA | 90kW | AC900 | AC900 | AC900 | ETS100 | 4 | 6 |
| EWAD420MZ-XS B2 | 3120-70Hz-DC | NA | 90kW | AC900 | AC900 | AC900 | ETS100 | 4 | 6 |
| EWAD450MZ-XS B2 | 3122-60Hz-DC | NA | 120kW | AC900 | AC900 | AC900 | ETS250 | 6 | 6 |
| EWAD540MZ-XS B2 | 3122-65Hz-DC | NA | 120kW | AC900 | AC900 | AC900 | ETS250 | 6 | 6 |
| EWAD570MZ-XS B2 | 3122-70Hz-DC | NA | 120kW | AC900 | AC900 | AC900 | ETS250 | 6 | 6 |
| EWAD610MZ-XS B2 | 3122-75Hz-DC | NA | 120kW | AC900 | AC900 | AC900 | ETS250 | 6 | 8 |
| EWAD660MZ-XS B2 | 3122-80Hz-DC | NA | 120kW | AC900 | AC900 | AC900 | ETS250 | 8 | 8 |
| EWAD680MZ-XS B2 | 3122-85Hz-DC | NA | 120kW | AC900 | AC900 | AC900 | ETS250 | 8 | 8 |
| EWAD770MZ-XS B2 | F3AS-67.5Hz-DC | NA | 200kW | AC900 | AC900 | AC900 | ETS250 | 8 | 8 |
| EWAD850MZ-XS B2 | F3AS-75Hz-DC | NA | 200kW | AC900 | AC900 | AC900 | ETS250 | 8 | 8 |
| EWAD910MZ-XS B2 | F3AL-70Hz-DC | NA | 200kW | AC900 | AC900 | AC900 | ETS250 | 8 | 10 |
| EWADC10MZ-XS B2 | F3AL-75Hz-DC | NA | 200kW | AC900 | AC900 | AC900 | ETS250 | 10 | 10 |
| EWADH10MZ-XS B2 | F3AL-80Hz-DC | NA | 200kW | AC900 | AC900 | AC900 | ETS250 | 10 | 12 |
| EWADC11MZ-XS B2 | F3AL-85Hz-DC | NA | 200kW | AC900 | AC900 | AC900 | ETS250 | 12 | 12 |

| Modello Daikin | Compressore | Opt. 260 Boost Comp | Inverter | Fan Type 50/60 Hz | Fan Brine 50/60 Hz | Fan Type Opt. 142 HA 50/60 Hz | Fan Type Opt.158 | EXV | FanC1 | FanC2 |
|-----------------|----------------|------------------------------|----------|----------------------|-----------------------|-------------------------------------|------------------------|--------|-------|-------|
| EWAD360MZ-PS B2 | 3120-60Hz-DC | NA | 90kW | DC1000L | DC1000L | DC1000L | STD | ETS100 | 4 | 6 |
| EWAD420MZ-PS B2 | 3120-70Hz-DC | NA | 90kW | DC1000L | DC1000L | DC1000L | STD | ETS100 | 4 | 6 |
| EWAD450MZ-PS B2 | 3122-60Hz-DC | NA | 120kW | DC1000L | DC1000L | DC1000L | STD | ETS250 | 6 | 6 |
| EWAD540MZ-PS B2 | 3122-65Hz-DC | NA | 120kW | DC1000L | DC1000L | DC1000L | STD | ETS250 | 6 | 6 |
| EWAD570MZ-PS B2 | 3122-70Hz-DC | NA | 120kW | DC1000L | DC1000L | DC1000L | STD | ETS250 | 6 | 6 |
| EWAD610MZ-PS B2 | 3122-75Hz-DC | NA | 120kW | DC1000L | DC1000L | DC1000L | STD | ETS250 | 6 | 8 |
| EWAD660MZ-PS B2 | 3122-80Hz-DC | NA | 120kW | DC1000L | DC1000L | DC1000L | STD | ETS250 | 8 | 8 |
| EWAD680MZ-PS B2 | 3122-85Hz-DC | NA | 120kW | DC1000L | DC1000L | DC1000L | STD | ETS250 | 8 | 8 |
| EWAD770MZ-PS B2 | F3AS-67.5Hz-DC | NA | 200kW | DC1000L | DC1000L | DC1000L | STD | ETS250 | 8 | 8 |
| EWAD850MZ-PS B2 | F3AS-75Hz-DC | NA | 200kW | DC1000L | DC1000L | DC1000L | STD | ETS250 | 8 | 8 |
| EWAD910MZ-PS B2 | F3AL-70Hz-DC | NA | 200kW | DC1000L | DC1000L | DC1000L | STD | ETS250 | 8 | 10 |
| EWADC10MZ-PS B2 | F3AL-75Hz-DC | NA | 200kW | DC1000L | DC1000L | DC1000L | STD | ETS250 | 10 | 10 |
| EWADH10MZ-PS B2 | F3AL-80Hz-DC | NA | 200kW | DC1000L | DC1000L | DC1000L | STD | ETS250 | 10 | 12 |
| EWADC11MZ-PS B2 | F3AL-85Hz-DC | NA | 200kW | DC1000L | DC1000L | DC1000L | STD | ETS250 | 12 | 12 |

9.3 Pump Inverter Settings (Table C)

| Impostazioni Parametri Inverter Danfoss per Pompe | | | | |
|---|-----------------------------|----------------------|--------------------|---|
| Start-up Wizard for Open Loop Applications | | | | |
| Parametro | Descrizione | Settings | Default | NOTE |
| 0-03 | Regional Settings | default | [0] International | |
| 0-06 | Grid Type | [12] 380-440V/50Hz | [12] 380-440V/50Hz | Verificare Tensione di alimentazione su R.M. |
| 1-10 | Motor Construction | default | [0] Asynchron | |
| 1-20 | Motor Power | default | Size related | Verificare Targa Motore |
| 1-22 | Motor Voltage | 400 V | Size related | Verificare Targa Motore |
| 1-23 | Motor Frequency | 50 Hz | Size related | Verificare Targa Motore |
| 1-24 | Motor Nominal Current | default | Size related | Verificare Targa Motore |
| 1-25 | Motor Nominal Speed | See Pump Motor Label | Size related | Verificare Targa Motore |
| 1-73 | Flying Start | default | [0] Disabled | |
| 3-02 | Minimum Reference | - | 0 | Con velocità comandata dal cliente, impostare a 40Hz. |
| 3-03 | Maximum Reference | 50 | 50 | Come 1-23 a meno che non sia riportata su R.M. una velocità inferiore |
| 3-41 | Ramp-Up Time | 10 s | Size related | Tempo per arrivare a 1-23 frequency |
| 3-42 | Ramp-Down Time | 10 s | Size related | Tempo per fermarsi da 1-23 frequency |
| 4-12 | Motor Speed Low Limit [Hz] | default | 0 | |
| 4-14 | Motor Speed High Limit [Hz] | default | 63 | |
| 4-19 | Max Output Frequency | default | Size related | |
| 5-40 | Function Relay [0] | default | Alarm | |
| 5-40 | Function Relay [1] | default | Drive running | |
| 6-10 | Terminal 53 Low Voltage | default | 0.07 V | |
| 6-11 | Terminal 53 High Voltage | default | 10 V | |
| 6-12 | Terminal 53 Low Current | default | 4 mA | |
| 6-13 | Terminal 53 Low Voltage | default | 20 mA | |
| 6-19 | Terminal 53 mode | default | 1 | Voltage input - [0] commuta all'ingresso in corrente |

9.4 Pre-Commissioning Sheet (Table D)



Pre-Commissioning Sheet

Job Name: _____

Unit Model No.(s): _____

Daikin Serial Unit No.: _____

| | Yes | No | N/A |
|---|--------------------------|--------------------------|--------------------------|
| Chilled Water | | | |
| -Piping complete | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| -Water System filled and vented | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| -Pumps installed & operational (rotation checked) | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| -Strainers installed and clean | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| -Controls (3-way valves, bypass valves, etc.) operable | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| -Flow switch installed | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| -Water system operated and flow balanced to meet unit design requirements | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| -Proper glycol percentage for the application in accordance with Daikin specifications | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| Condenser Water | | | |
| -Cooling tower flushed, filled and piping vented | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| -Pumps installed & operational (rotation checked) | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| -Strainers installed and clean | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| -Controls (3-way valves, bypass valves, etc.) operable | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| -Water system operated and flow balanced to meet unit design requirements | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| -Proper glycol percentage for the application in accordance with Daikin specifications | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| Electrical | | | |
| -Power leads connected to unit main terminal block | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| -Power leads have been checked for proper electrical phasing U-V-W for L1, L2, & L3 respectively. | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| -All interlock wiring complete and complies with Daikin specifications | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| -Pump starter and interlocks wired | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| -Cooling tower fans and controls wired | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| -Wiring complies with National Electrical Code and local codes | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| Miscellaneous | | | |
| -Unit installed in accordance with Daikin IOM specifications (leveling, space requirements, ...) | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| -Thermometer wells, thermometers, gauges, control wells, controls, etc., installed | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| -A minimum system load of 60% of machine capacity is available for testing and adjusting controls | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |

Warning: Under no condition should these units be started prior to the authorized start-up by Daikin Applied. Failure to follow this warning may result in serious equipment damage and will negate the warranty.

All installation work has been completed as checked above; the system has been inspected and the unit is ready for start-up


Site Engineer

Name: _____

Date: _____

Signature: _____

9.5 Commissioning Sheet (Table E)

|  | | CHILLER COMMISSIONING SHEET - EWAD-TZ | | | |
|---|--|---|--|--|--|
| End user: | | Date: | | | |
| Site: | | Model nr: | | | |
| Distributor: | | Serial nr: | | | |
| A PRE-POWER ON CHECK LIST | | D STARTUP CHECK LIST | | | |
| A1 Any shipping damage? | | D1 Running Adjustments performed (calibrations)? | | | |
| A2 Is the chiller adequately level mounted? | | D1 Safety tests performed? | | | |
| A3 Are minimum space requirements met? | | DATA ACQUISITION Mode: Chiller Percentage of Load: C1 C2 Circuit: C1 C2 | | | |
| A4 Anti vibration pads installed? | | D1 ELECTRICAL SYSTEM | | | |
| A5 Full Leak Test performed? | | D1.1 Comp running Amps L1 (A) | | | |
| A6 Water piping system checked? | | D1.2 Comp running Amps L2 (A) | | | |
| A7 Water Flows checked? | | D1.3 Comp running Amps L3 (A) | | | |
| A8 Glycol type / percentage [Evap/Cond] | | D2 REFRIGERANT SYSTEM | | | |
| A9 Are electrical connections correct? | | D2.1 Evaporator Pressure (kPa) | | | |
| A10 Compressor model C1 | | D2.2 Condenser Pressure (kPa) | | | |
| A11 Compressor serial C1 | | D2.3 Suction Temperature (°C) | | | |
| A12 Compressor model C2 | | D2.4 Condenser Pressure (kPa) | | | |
| A13 Compressor serial C2 | | D2.5 Suction Temperature (°C) | | | |
| B PRE-STARTUP CHECK LIST | | D2.6 Discharge Superheat (°C) | | | |
| B1 Evaporator Flow Switch Check | | D2.7 Liquid Temperature (°C) | | | |
| B2 Condenser Flow Switch Check | | D2.8 Liquid Pressure (kPa) | | | |
| B3 Main VOLTAGE L1-L2 (V) | | D2.9 Subcooling (°C) | | | |
| B4 Main VOLTAGE L2-L3 (V) | | D2.10 Subcooling at dryer filter (°C) | | | |
| B5 Main VOLTAGE L1-L3 (V) | | D2.11 Evaporator Approach (°C) | | | |
| B6 Frequency (Hz) | | D2.12 Condenser Approach (°C) | | | |
| B7 Control voltage Tx IN / OUT (V) | | D2.13 Oil Pressure (kPa) | | | |
| B8 Control voltage AL1 (V) | | D2.14 Oil Pressure Differential (kPa) | | | |
| B9 Oil Heaters were on before start up? | | D2.15 EXV Position (%) | | | |
| B10 Check Heaters (A) (measure current) | | D2.16 Fans (%) | | | |
| | | D2.17 Economizer/Subcooler Status | | | |
| B11 Unit Software Version | | D2.18 Economizer EXV Position (%) | | | |
| B12 Unit Water Temp Set Point Cool/Heat (°C) | | D3 EVAPORATOR (WATER) | | | |
| B13 Unit settings checked? | | D3.1 Entering Water Temperature (°C) | | | |
| B14 Circuit settings checked? | | D3.2 Leaving Water Temperature (°C) | | | |
| B15 Alarm Limits set? | | D3.3 Evaporator Pressure Drop (kPa) | | | |
| B16 Evap Water Frz Alarm Setpoint (°C) | | D3.4 Design Evaporator Pressure Drop (kPa) | | | |
| B17 Dry Test performed? | | D3.5 Flow Rate (l/s) | | | |
| B18 Can be the chiller put into operation? | | D3.6 Design Flow rate (l/s) | | | |
| C PRE-STARTUP COMMENTS | | D3.7 Check Flow Switch status | | | |
| | | D5 CONDENSER (AIR) | | | |
| | | D4.1 UNIT IN Air Temperature (°C) | | | |
| E POST-STARTUP COMMENTS | | | | | |
| | | | | | |
| F Defective items found at commissioning? | | | | | |
| 1 Parts subject to ECHC? | | | | | |
| 2 Parts requested to be directly supplied by factory? | | | | | |
| Please mention under which conditions parts are directly requested to the factory (ie. Urgent matter, Extra Europe affiliate or others): | | | | | |
| G Present during commissioning | | | | | |
| Name : | | Company: | | | |
| Name : | | Company: | | | |
| Name : | | Company: | | | |
| Author: | | Installer: | | | |
| Signature: | | Signature: | | | |
| Title: Service Engineer | | Title: | | | |
| <p>As Commissioning is a technical process performed - before the Chiller is put into definitive operation - by an "Authorised Engineer".</p> <p>As Commissioning is done and is intended to achieve the following specific limited objectives:</p> <ul style="list-style-type: none"> - verify and document (via checklist) that the Chiller is installed according to the manufacturers installation manual and operation manual. - configure the Chiller to a set of manufacturers defined parameters in order to secure the correct performance of the Chiller in the specific site related operating conditions. <p>Therefore the Commissioning process does not take away from or reduce the responsibility of the System Designers and/or Installers to provide a finished and fully functioning system.</p> | | | | | |